

**Reply of Pre Bid Queries [LOT-1\_dt. 08.08.2023]**

**NAME OF WORK : BALANCE JOB OF SUPPLY, ERECTION, TESTING & COMMISSIONING OF PERMANENT RAW WATER SUPPLY SYSTEM AND ALLIED FACILITIES AT TALCHER FERTILIZERS LIMITED, ANGUL, ODISHA**

**TENDER NO : PNP/PC-150/E-121/NCB dated 21.07.2023**

SL. NO.	REFERENCE OF BIDDING DOCUMENT				BIDDER'S QUERY	PDIL'S REPLY
	SEC. NO.	Page No.	Clause No.	Subject		
1			General	Schematic Diagram	Since the scope under this tender is Balance works type; Bidder requests to provide the chart or diagram showing chainage wise and exact location wise balance activities, so that bidder can understand the exact location of balance activities which is very much necessary for costing purpose and to quote correct prices.	Scope has been described in NIT clearly. Kindly follow NIT. For further clarity bidder may visit to site to ascertain actual site condition.
2			General	Alignment Sheets and Crossings Drawings	Bidder requests to provide the Alignment Sheets for entire route and Crossings Drawings envisaged in the referred tender.	As per NIT, Route survey is under scope of bidder. Crossings has been described in NIT.
3	V	279	40.0	TERMS OF PAYMENT	The payment terms for Electrical, Instrumentation and Cathodic Protection Items are not stipulated specifically. Bidder requests to provide the payment terms for the supply items and also for Installation items.	No Change. Same shall be as per NIT.
4	SOR	1184	34.10	RADIOGRAPHY for 36" NB	Bidder understands that the payment or Radiography NDT shall be paid separately under SOR Item no. 34.10 against each joint of NDT RT taken for main pipeline and therefore the prices of NDT RT shall not be quoted under mainline item no. 5.13. Please confirm.	Bidder understanding is Correct.
5	SOR	1176	5.13 to 5.16	Main Pipeline description: Inner Lining/ Painting	Bidder requests to confirm whether the Inner lining/Painting would be required at Inner side of joints after welding? If yes, Bidder requests to provide the specification and approved for the same.	Confirmed. Entire Pipelines shall be provided with internal lining as two component, 100% solid, solvent free liquid epoxy with 500micron total DFT(min.). Please refer PNP/PC150/E121/SEC-IV. 6.0 Sheet 39 of 66

**Reply of Pre Bid Queries [LOT-1\_dt. 08.08.2023]**

**NAME OF WORK : BALANCE JOB OF SUPPLY, ERECTION, TESTING & COMMISSIONING OF PERMANENT RAW WATER SUPPLY SYSTEM AND ALLIED FACILITIES AT TALCHER FERTILIZERS LIMITED, ANGUL, ODISHA**

**TENDER NO : PNP/PC-150/E-121/NCB dated 21.07.2023**

SL. NO.	REFERENCE OF BIDDING DOCUMENT				BIDDER'S QUERY	PDIL'S REPLY
	SEC. NO.	Page No.	Clause No.	Subject		
6				General	<p>Since this is balance works: Bidder requests TALCHER/PDIL to take the sole responsibility to clear &amp; settlement of any pending liabilities of previous contractor to their vendors, sub agencies, land owners, local authorities, etc. and also requests to provide the hindrance free work front to new contractor, in order to achieve the project completion in stipulated timeline. Bidder or new contractor shall not be held responsible and liable to pay any of liabilities of previous contractor. Please confirm.</p>	Liabilities of Previous Contractor does not cover under bidder's scope.
7				General	<p>There is no provision of Idle Charge compensation in the contract. Bidder requests to keep the provision of Idle charge compensation to contractor which shall be subject to delay or non-availability of work front or permission from the side of PDIL/TALCHER.</p>	No Change. NIT Condition shall prevail.
8	Sec-I IFB	4	K	DUE DATE & TIME OF BID-SUBMISSION	<p>Current bid submission due date is 10.08.2023 which is very short time. Bidder requests to extend the bid submission due date at least upto 30.08.2023 as Bidder needs to get the quotation of various supply items from the respective approved vendors. Vendors are also requesting to provide sufficient time for submission of their quotation. Therefore, the extension till 30.08.2023 would be required.</p>	No Change. Same shall be as per NIT.